





## **TH627**

## **Telehandler**

Maneuverable and effective.

If stacking heights of 6 meters are involved, the telehandler TH627 is the ideal solution. With a payload of 2.7 metric tonnes, it remains stable even during extreme loading processes. The numerous option variants make the TH627 a real all-rounder on the construction site. With two cabin variants, the vehicle offers a low overall height or, with the high cabin, an even better all-round visibility.

## Highlights

■ Choice between two cab heights.

## **Technical Data**

Ну	dr	au	lic

Operating pressure hydraulics 260.0 bar

Flow rate max. 89.0 l/min

Mechanical - Output Details

Travel speed 20.0 km/h

Travel speed (Option) 30.0 km/h

Mechanical Details

Length 4,400.0 mm

Width 1,960.0 mm

Height	2,105.0 mm			
Weight	5,000.00 kg			
Payload max.	2,700.0 kg			
Payload max. LSP 500mm	2,700.0 kg			
Payload lift max.	1,800.0 kg			
Lift max.	5,730.0 mm			
Lift bucket swivel	6,080.0 mm			
Engine				
Maximum torque	300.0 Nm			